# ENGINEERING DEPARTMENT.

## SHIMOGA DIVISION.

*Notice dated 23rd March 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, upto Noon of 24th April 1930 for restoring Veregara Bhairanakoppa Anicut-breaches Regd. No. 234 of Kumsi Sub-Fields. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, local instructions and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 250 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Veregara Bhairanakoppa Anicut-breaches Regd. No. 234 of Kumsi Sub-Fields, in default of which, tenders will be rejected.

5. The usual acceptance or rejection will rest with the Executive Engineer, Shimoga Division, who does not bind himself to accept the highest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual security bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Veregara Bhairanakoppa Tank Regd. No. 234, in Kumsi Sub-Fields.

| No. | Items of work | Unit | Quantity |
|---|---|---|---|
| | *I. Bund top width 15 feet R. L. 55·00.* | | |
| 1 | Clearing and cutting grips etc., complete | Lump sum | |
| 2 | Earthwork to bund, including excavating carrying putting, and consolidating etc., complete. | C.yd. | 6,790 |
| 3 | Turfing front and rear slopes | Sqrs. | 468·72 |
| 4 | Providing and fixing grade stones with bed slabs including figuring and fixing etc. complete | No. | 11 |
| 5 | Do do index stones 5½ | " | 11 |
| 6 | Do date and Reg. No. stone do | " | 1 |
| 7 | Do gauge stone 15' long do | " | 1 |
| 8 | Do B. M. stones with bed slabs do | " | 2 |
| | *II. Constructing No. 1 sluice at C. S. 8 R. L. 51·00.* | | |
| 1 | Earthwork excavation | C.yd. | 40 |
| 2 | Refilling the same with consolidation | " | 3 |
| 3 | Stone jelly concrete in surki mortar | C.ft. | 127 |
| 4 | Burnt stone in surki mortar | " | 376 |
| 5 | Burnt stone slabs 4½" to 6" thick dressed and fixed | S.ft. | 54 |
| 6 | Pointing with surki mortar | Sqrs. | 2·00 |
| 7 | Cutting orifice holes | Lump sum | |
| 8 | Cast iron pipes 6" dia including fly, freight carting to spot and fixing with cement joints complete only fixing charges to be quoted. | R.ft. | 27 |
| 9 | Providing hardwood plug, with iron rod with locking arrangements complete. | Lump sum | |
| | *III. Constructing No. 2 sluice at C. S. 9 R. L. 47·00.* | | |
| 1 | Earthwork excavation | C.yd. | 26 |
| 2 | Refilling, the same with consolidation | " | 20 |
| 3 | Stone jelly concrete in surki mortar | C.ft. | 104 |
| 4 | Burnt stone in surki mortar | " | 287 |
| 5 | Pointing with surki mortar | Sq. | 3·00 |
| 6 | Burnt stone slabs 4½" to 6" thick dressed and fixed | S.ft. | 43 |

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 7 | Cutting orifice holes ... ... ... | Lump | sum |
| 8 | C. I. pipes 5" dia. including, Rly. freight, carting to spot and fixing with cement joint only fixing charges to be quoted. | R.ft. | 24 |
| 9 | Providing teakwood plug with iron rod with locking arrangements, etc., complete. | Lump | sum |
| | *IV. Left natural gauge weir 20' long R. L. 52·00* | | |
| 1 | Clearing draft channel ... | Lump | sum |
| 2 | Rough stone work new ... | C.yd. | 15 |
| | *V. Constructing rigid apron 20' long R. L. 52·00* | | |
| 1 | Earthwork excavation ... | C.yd. | 14 |
| 2 | Stone jelly concrete in sand mortar ... | C.ft. | 39 |
| 3 | Rich stone in sunki mortar ... | " | 73 |
| 4 | Burma stone slabs 4½" to 6" thick dressed and ... | S.ft. | 26 |
| 5 | Sunki mortar pointing ... | " | 100 |
| 6 | Rough stone work in ... | C.yd. | 36 |

SRINIVASA CHARI,
*Executive Engineer.*

## KADUR DIVISION.

*Abstract Notification dated 26th March 1930.*

Attention of the public is invited to the notice calling for tenders for constructing Incomplete Middle School Building at Jagatagere, Kadur Taluk in pages 385 to 386 of Part IV of *Mysore Gazette*, of dated 27th March 1930. The last date for receiving tender is 4th April 1930 till 3-30 P.M.

---

*Dated 27th March 1930.*

"The public are hereby informed that the Traveller's Bungalow at Kottigehalli, Madgere Taluk will be used as the 4th, 5th and 6th April 1930 for travellers as it is reserved for the purpose of Election Polling."

L. S. H. WINKLER,
*Executive Engineer.*

## MYSORE DIVISION.

*Dated 24th March 1930.*

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, pages 373 and 374, Part VI dated 27th March 1930 intimating the last date of tenders for restoring Kaigonahalli tank, Reg. No. 50 of Krishnarajanagar Taluk, Mysore District.

---

*Dated 19th March 1930.*

"Reference is invited to the advertisement published in the *Mysore Gazette*, dated intimating the last date of tenders for restoring Alya tank in Nanjangud Taluk, Part VI, pages 351 to 352, dated 27th March 1930."

T. S. IYENGAR,
*Executive Engineer.*

## CHITALDRUG DIVISION.

*Dated 17th March 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 25th April 1930, for Restoring Hirigal Minor Tank R. No. 142 of Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1930.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.